BRUHATH BANGALORE MAHANAGARA PALIKE
RAJARAJESHWARI NAGARA DIVISION
SCHEDULE B

NAME OF WORK: Beautification and construction of compound wall with Grill to Indira Canteen in ward no16

Sl. No	Qty	Description of work	Unit	Tender Rate	
				In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	12.77	Dismantling burnt brick masonry in clay mortar/lime mortar/cement mortar and stacking the bricks within a radius of 50m and removing the debris to a distance upto 200m.	Cum	168.48	Rupees One Hundred Sixty Eight And Paise Forty Eight Only
2	33.50	Removing B.S. slab of Drain and stacking	Sqm	66.96	Rupees Sixty Six And Paise Ninety Six Only
3	315.00	Ecarthwork in surface excavation in ordinary soil for levelling and lowering the ground manually (other than foundation of buildings, culverts, road drains and trenches of pipe line and cables) and removing the excavated distance not exceeding 50m and lift upto 1.5m, excavated surface levelled and neatly dressed, disposed earth to be levelled after breaking of clods and neatly dressed as per specifications	Cum	169.56	Rupees One Hundred Sixty Nine And Paise Fifty Six Only
4	116.71	Earthwork excavation for the foundations of the buildings,water supply,sanitary line and electrical conduits either in pits or in trenches 1.5m and above in width in hard soil not exceeding 1.5 m in depth including dressing the bottom and sides of the pits and trenches,stacking the excavated soil clear from the excavations with lead upto 50m after breaking of clod complete a per specifications	Cum	305.64	Rupees Three Hundred Five And Paise Sixty Four Only
5	13.28	Providing and layering in position plain cement concrete of mis 1:3:6 with opc cement @220kgs with 40mm and down size graded granite metal coare aggrefate @0.892 cum and fine aggreagate @0.465 cum machine mixed,machine mixed,concrete laid in layers not exceeding 15 cms,thick,well compacted, in foundation including cost of all materials,labour,Hom of machinery,curing complete as per specification	Cum	5449.68	Rupees Five Thousand Four Hundred Forty Nine And Paise Sixty Eight Only
6	74.37	Providing and constructing granite / trap / basalt size stone masonry in basement with cement mortar 1:6 edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications.	Cum	5405.40	Rupees Five Thousand Four Hundred Five And Paise Forty Only

Executive Engineer-3
KRIDL, BBMP, Bangalore

Signature of the Contractor

Executive Engineer
RRNagara Division
EE (RRND)

Scanned by CamScanner

7	11.50	Providing and laying in position Plain cement concrete of mix1:2:4 with cement @240Kgs,with 20mm and down size graded granite metal coarse aggregates @ 0.878Cum and fineaggregtes @0.53Cum, machine mixed, concrete laid in layers not exceeding 15 cms. Thick, well compacted, in foundation, plinth and cills, including cost of all materails, labour, HOM of machinery, curing complete as per specifications.	Cum	5876.28	Rupees Five Thousand Eight Hundred Seventy Six And Paise Twenty Eight Only
8	60.30	Providing ruled pointing to coursed stone masonry with CM1:3,20mm deep after raking joints to depth of 20mm nicely lining,including cost of materials,labour,curring complete as per specification	Sqm	105.84	Rupees One Hundred Five And Paise Eighty Four Only
9	113.40	Providing and constructing load bearing wall with solid concrete blocks density not less than 1800 kg / m3 having a minimum average compressive strength of 5.00 n/mm2 confirming to IS 2185 (part1):2005 and constructed with CM1:4 as per IS 2572:2005 including cost of materials, labourcharges,scaffolding,curing complete as per specifications.	Sqm	897.48	Rupees Eight Hundred Ninety Seven And Paise Forty Eight Only
10	33.50	Refixing stone slabs ob drains and pointing in C.M.	Sqm	82.08	Rupees Eighty Two And Paise Eight Only
11	316.40	Supply ,collecting and spreading good quality gravel and formation etc complete	Cum	308.88	Rupees Three Hundred Eight And Paise Eighty Eight Only
12	260.40	Supply ,collecting and spreading good quality stone dust/grit and formation etc complete	Cum	989.28	Rupees Nine Hundred Eighty Nine And Paise Twenty Eight Only
13	1680.00	Fabricating, providing and erecting in positon of Hot dip galvanised M/S Ornamental Security grill using 75X12mm M.S Flat for alroung frame work with verticals at the centr and horizontal centere support M.S square of 20X20 mm of dirrerent heights as shown in the drawing are to be fixed at 16 cms C/C for bottom rods providing ornamental C I Designers at the botom and C I arrows in the midle and top. Tje entrire frame work is to be fixed by means of expansion bolts to th brick pillars with necessary driling holes, the work includes providing wto coats of enamel painting over one coat of red lead ready mix primer coat etc complete cost of all labour, painting, erection charges using hoist pulleycranes with all lead and lift, loading, transporting and unloading using hoist pulley cranes, scaffolding charges and all other incdental charges required for successful completion of the work as per specification and drawings.	Sqm	171.72	Rupees One Hundred Seventy One And Paise Seventy Two Only
14	235.55	Providing 18mm thick cement plaster in single coat wigh cement mortar 1:3, to brick masonry including rounding off corners wherever required somooth rendering, : Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications	Sqm	263.52	Rupees Two Hundred Sixty Three And Paise Fifty Two Only

Executive Engineer-3
KRIDL, BBMP, Bangalore
Signature of the Contractor

Executive Engineer
RRNagara Division
BBMP
EE (RRND)

Scanned by CamScanner

15	210.25	Providing and applying painting in two coats with plastic emulsion paint of approved brand on wall surface to give an even approved shade after thoroughly brushing the surface , free from mortar drops and other foreign matter including preparing the surface even and sand paper smooth, cost of materials, labour, complete as per specifications.	Sqm	97.20	Rupees Ninety Seven And Paise Twenty Only
16	386.80	Providing and finishing external walls in two coats with waterproof cement paint of approved brand and shade to give an evern shade after throughly brooming the surface to remove all dirt and loosed powdered material,free from mortar drops and other foreign matter cost of materials, labour, complete as per specifications.	Sqm	90.72	Rupees Ninety And Paise Seventy Two Only
17	50.00	Providing and fixing to wall,ceiling and floor,medium density polyethylene pipies 6.00 Kg/sq.cm working pressure 160mm outside diameter with special flange,compression type fittings,wall clips,making good the wall,ceiling and floor including cost of all materials,labour charges,HOM of equipments and testing complete as per specifications	rmt	651.24	Rupees Six Hundred Fifty One And Paise Twenty Four Only
18	50.00	Providing and fixing Chorinatyed Pily Veny Chlorde (CPVC) pipes conforming to IS:15778, having thermal sstability for hot and cold water supply including all CPVC plain and brass threaded fittings, this includes jointing of pipes and fittings with one step solvent cement, trenching, refilling &tresting of joints compltete	rmt	183.60	Rupees One Hundred Eighty Three And Paise Sixty Only
19	123.20	Providing and laying heavy duty cobble stones75mm thick interlock pavers using cement and course sand for manufacture of block of approved size shape and colour with a minimum compressive strength of 281 kg per sqm over 50mm thick sand bed (average thickness) and compacting with plate vibrator having 3 tons compaction force thereby forcing part of sand underneath to come up in between joints, final compaction of paver surface joints into its final level, including cost of materials, labour and HOM of machineries complete as per specifications.	Sqm	1047.60	Rupees One Thousand Forty Seven And Paise Sixty Only
20	6.00	Providing and fixing the Granite Benches	nos	10550.00	Rupees Ten Thousand Five Hundred Fifty Only
21	515.61	Conveying the excavated earth slit debris and over burden earth etc.,to a lead of 10 to 15kms distance by using private vehicle thi include the cost of loading and unloading charges etc.,complete,	Cum	116.00	Rupees One Hundred Sixteen Only

Executive Engineer-3
KRIDL, BBMP, Bangalore

Executive Engineer
RRNagara Division
BBMP

Signature of the Contractor

Scanned by CamScanner